

Annexure 1

Scope of electrification work of Cherukod Branch ATM

All the rate should include the cost of material and labour

Sl.No	Particulars	Item No's	Unit Rate	Total Amt
1	10 Sqmm x 4core UG Cable (Vguard, E-Fab,Poly Cab)	Aproximate 15 mtr		
2	6 Sqmm x 2core UG Cable (Vguard, E-Fab,Poly Cab)	Aproximate 45 mtr		
3	Cat 6 land Cable	Aproximate 135 mtr		
4	Copper Plate earthing 60x60, thickness 25x3	1 No's		
5	TPN DDB Setting(Lgrand,L&T)	1 No's		
6	UPS DB Setting (Lgrand,L&T)	1 No's		
7	LED Panel Light 15 wt(Branded Item)	4 No's		
8	Wall Fan 16 inch high speed	1No's		
9	UPS 16 amps socket	2 No's		
10	AC power point	1 No's		
11	6 amp Socket	1 No's		
12	18 w LED Tube	1 No's		
13	Exhaust Fan 6 Inch	1 No's		
14	Board light Connection including timer	1 No's		
15	RJ 45 LAN Cable point (D link)	2 No's		
	TOTAL			

Annexure II

Scope of electrification work of Pandikkad Branch ATM

All the rate should include the cost of material and labour

Sl.No	Particulars	Item No's	Unit Rate	Total Amt
1	10 Sqmm x 4core UG Cable (Vguard, E-Fab,Poly Cab)	Aproximate 48 mtr		
2	6 Sqmm x 2core UG Cable (Vguard, E-Fab,Poly Cab)	Aproximate 48 mtr		
3	Cat 6 land Cable	Aproximate 135 mtr		
4	Copper Plate earthing 60x60, thickness 25x3	1 No's		
5	TPN DDB Setting(Lgrand,L&T)	1 No's		
6	UPS DB Setting (Lgrand,L&T)	1 No's		
7	LED Panel Light 15 wt(Branded Item)	4 No's		
8	Wall Fan 16 inch high speed	1No's		
9	UPS 16 amps socket	2 No's		
10	AC power point	1 No's		
11	6 amp Socket	1 No's		
12	18 w LED Tube	1 No's		
13	Exhaust Fan 6 Inch	1 No's		
14	Board light Connection including timer	1 No's		
15	RJ 45 LAN Cable point (D link)	2 No's		
	TOTAL			

Annexue III

Scope of Interior furnishing work of Cherukod Branch ATM

All the rate should include the coast of material and labor

Sl.No	Item description	Area measurement	Unit rate	Total Amt
ATM Door				
1.	2 _{1/2} x 1 _{1/2} section heavy door frame of 2 kg weight , heavy door chanel (clip, rubber beeding, 6mm or 8mm toughened glass with SS handle, floor spring.	63 sq ft		
ATM Partition				
1.	1 _{1/2} x 1 Section heavy door frame of 1.100 kg weight, with good quality ACP exterior sheet with net cutting.	51 sq ft		
Fiber Sealing				
1.	1 _{1/2} x 1 Section heavy Cournish 7mm sheet.	78 sq ft		
	TOTAL			

Annexure IV

Scope of Interior furnishing work of Pandikkad ATM

All the rates should include the cost of material and labour

Sl.No	Item description	Area measurement	Unit rate	Total Amt
ATM Door				
1.	2 $\frac{1}{2}$ x 1 $\frac{1}{2}$ section heavy door frame of 2 kg weight , heavy door chanel (clip, rubber bedding, 6mm or 8mm toughened glass with SS handle, floor spring.	32.sq ft		
ATM Partition				
1.	1 $\frac{1}{2}$ X 1 Section heavy door frame of 1.100 kg weight, with good quality ACP exterior sheet with net cutting.	42 sq ft		
Fiber Sealing				
1.	1 $\frac{1}{2}$ X 1 Section heavy Cournish 7mm sheet.	36 sq ft		
Side covering				
1.	Side covering with good quality ACP exterior sheet	59 sq ft		
	TOTAL			

Total cost of electrification work of Cherukode and Pandikkad Branch

Name of Branch	
Cherukode (As per annexure I)	
Pandikkad (As per Annexure II)	
Total	

Total cost of Interior furnishing work of Cherukode and Pandikkad Branch

Name of Branch	
Cherukode (As per annexure III)	
Pandikkad (As per Annexure IV)	
Total	